

ADDENDUM #2

Bid Clarifications

1. See attachment for sign in sheet for mandatory site walk for bidding demolition subcontractors, which includes a copy of the package that was distributed at the walkthrough. This includes schedule/sequence for demolition work
 - a. As discussed at demolition site walk – abatement and building demolition will begin on the south of the site at the portable buildings. All structures, trees, shrubs, and planters located between the main building and the classroom building is to be included in the building demolition subcontractor scope. All furniture not attached to the buildings will be removed before construction begins. Abatement scope will include removing all refrigerant from all mechanical equipment. All existing underground utilities to be demolished and removed.
 - b. See attached photos of existing cafeteria that wasn't able to be accessed during job walk. Building demolitions subcontractor to be responsible for demolitions/removal of all existing cafeteria tables, equipment, and kitchen hood.
2. For abatement subcontractors – bid the quantities provided in the Vista Hazmat Survey. District will carry allowance for any unforeseen quantities.
3. There is a discrepancy between the plans and specifications for the material to be used for toilet partitions. Please bid toilet partitions as per the specifications for materials.
4. The cutoff for pre-bid RFI's to be answered is 4pm April 19, 2019